





Volume Report
Subgrade vs. Stripped

Name	Group	Code	Total	Cut	Area Fill	OnGrade	Volume Cut	Fill	Comp/Ratio Cut	Fill	Compact Cut	Fill	Export -Import	Change Per 0.1 ft
PHASE 1... Sub:	PHASE 1 CUT FILL AREA		311,405	165,015	130,522	15,868	7,950	7,815	1.20	1.00	9,540	7,815	1,725	1,156
PHASE 2... Sub:	PHASE 2 CUT FILL AREA		185,010	182,333	1,559	1,118	19,285	36	1.20	1.00	23,142	36	23,106	685
Regions Total			496,415	347,348	132,081	16,986	27,235	7,851			32,682	7,851	24,831	1,841

Stripping Qtys	Group	Code	Plane Area	Slope Area	Depth	Volume
TS Sub:	TS		496,415	496,440	0.500	9,193
Stripping Total			496,415	496,440		9,193

Job
 Depth Bracket Summary (Cover vs. Invert), Units Ft-CY
 All Classes (23) - All Phases (2)
 Wed Feb 18, 2026 15:50:09
 Page 1 of 1

Structure	Count	Average		0-4	4-6	6-8	8-10	10-12	12-14	14+
		Depth	Measure							
HDPE 08" PIPE	2	5.56	1,559.35	0.00	1,271.86	287.48	0.00	0.00	0.00	0.00
PVC 02" SCH 40 WATER LINE	6	4.35	1,246.69	292.20	954.50	0.00	0.00	0.00	0.00	0.00
PVC 04" SDR26 PIPE	2	4.14	740.49	363.53	273.72	103.24	0.00	0.00	0.00	0.00
INLET CATCH BASIN	9	5.00		0.00	9.00	0.00	0.00	0.00	0.00	0.00
PVC 02" WM	2	4.99		0.00	2.00	0.00	0.00	0.00	0.00	0.00
PVC 02" RPZ	2									
PVC 04" SDR26 45 BEND	2									
Totals										

Job
 Trench Volume Summary, Units Ft-CY
 All Classes (23) - All Phases (2)
 Wed Feb 18, 2026 15:50:20
 Page 1 of 1

Structure	Phase	Measure	Excavate	Native Backfill	Backfill	Bedding	Cover	Export -Import
HDPE 08" PIPE	PHASE 1	1,559.35	1,075.81	691.75	691.75	86.63	271.35	384.06
PVC 02" SCH 40 WATER LINE	PHASE 1	1,246.69	453.96	298.51	298.51	46.18	107.82	155.45
PVC 04" SDR26 PIPE	PHASE 1	740.49	324.32	198.05	198.05	34.28	89.35	126.27
Totals		3,546.53	1,854.09	1,188.31	1,188.31	167.09	468.52	665.78

Job
Structure Summary
 All Classes (23) - All Phases (2)
 Wed Feb 18, 2026 15:49:45
 Page 1 of 1

Structure	Material	Phase	Class	Measure	Section	Multiplier
ADA ACCESSIBLE MARKING	ADA ACCESSIBLE MARKING	PHASE 1 42 - Specialty Work		522.91	1.0000	1.00000000
ADA ACCESSIBLE MARKING SYMBOL	ADA ACCESSIBLE MARKING SYMBOL	PHASE 1 42 - Specialty Work		9.00	1.0000	1.00000000
BOLLARD 6"	BOLLARD 6"	PHASE 1 28 - Curb Sidewalk Pads Pavers & Bollards		36.00	1.0000	1.00000000
BUILDING 6" / 6"	STONE SUBBASE	PHASE 1 14 - Building Related		65,626.14	0.5000	0.03703700
BUILDING 6" / 6"	CONCRETE	PHASE 1 14 - Building Related		65,626.14	0.5000	0.03703700
CONC PAVE 6" / 6"	STONE SUBBASE	PHASE 1 28 - Curb Sidewalk Pads Pavers & Bollards		5,435.78	0.5000	0.03703700
CONC PAVE 6" / 6"	CONCRETE	PHASE 1 28 - Curb Sidewalk Pads Pavers & Bollards		5,435.78	0.5000	0.03703700
CURB 6" X 8" X 18"	CURB 6" X 8" X 18"	PHASE 1 28 - Curb Sidewalk Pads Pavers & Bollards		6,300.57	1.0000	1.00000000
DIRECTIONAL ARROW	DIRECTIONAL ARROW	PHASE 1 42 - Specialty Work		30.00	1.0000	1.00000000
HD 2.0" / 4.0" / 6.0"	ASPHALT TOP	PHASE 1 34 - Asphalt Paving		188,822.06	0.1667	0.03703700
HD 2.0" / 4.0" / 6.0"	ASPHALT BASE	PHASE 1 34 - Asphalt Paving		188,822.06	0.3334	0.03703700
HD 2.0" / 4.0" / 6.0"	STONE SUBBASE	PHASE 1 34 - Asphalt Paving		188,822.06	0.5000	0.03703700
HDPE 08" PIPE	SELECT	PHASE 1 20 - Storm		1,559.35	0.0000	0.03703700
HDPE 08" PIPE	COVER	PHASE 1 20 - Storm		1,559.35	4.6983	0.03703700
HDPE 08" PIPE	DISPLACEMENT	PHASE 1 20 - Storm		1,559.35	0.4517	0.03703700
HDPE 08" PIPE	BEDDING	PHASE 1 20 - Storm		1,559.35	1.5000	0.03703700
HDPE 08" PIPE	SPOIL	PHASE 1 20 - Storm		1,559.35	6.6500	0.03703700
INLET CATCH BASIN	INLET CATCH BASIN	PHASE 1 20 - Storm		9.00	1.0000	1.00000000
PARKING STALL MARKING	PARKING STALL MARKING	PHASE 1 42 - Specialty Work		5,300.48	1.0000	1.00000000
PAVEMENT MARKING	PAVEMENT MARKING	PHASE 1 42 - Specialty Work		454.73	1.0000	1.00000000
PVC 02" RPZ	PVC 02" RPZ	PHASE 1 22 - Water		2.00	1.0000	1.00000000
PVC 02" SCH 40 WATER LINE	Select	PHASE 1 22 - Water		1,246.69	0.0000	0.03703700
PVC 02" SCH 40 WATER LINE	Cover	PHASE 1 22 - Water		1,246.69	2.3353	0.03703700
PVC 02" SCH 40 WATER LINE	Displacement	PHASE 1 22 - Water		1,246.69	0.0314	0.03703700
PVC 02" SCH 40 WATER LINE	Bedding	PHASE 1 22 - Water		1,246.69	1.0000	0.03703700
PVC 02" SCH 40 WATER LINE	Spoil	PHASE 1 22 - Water		1,246.69	3.3667	0.03703700
PVC 02" WM	PVC 02" WM	PHASE 1 22 - Water		2.00	1.0000	1.00000000
PVC 04" SDR26 45 BEND	PVC 04" SDR26 45 BEND	PHASE 1 18 - Sanitary		2.00	1.0000	1.00000000
PVC 04" SDR26 PIPE	SELECT	PHASE 1 18 - Sanitary		740.49	0.0000	0.03703700
PVC 04" SDR26 PIPE	COVER	PHASE 1 18 - Sanitary		740.49	3.2580	0.03703700
PVC 04" SDR26 PIPE	DISPLACEMENT	PHASE 1 18 - Sanitary		740.49	0.0962	0.03703700
PVC 04" SDR26 PIPE	BEDDING	PHASE 1 18 - Sanitary		740.49	1.2500	0.03703700
PVC 04" SDR26 PIPE	SPOIL	PHASE 1 18 - Sanitary		740.49	4.6042	0.03703700
SIDEWALK 4" / 4"	STONE SUBBASE	PHASE 1 28 - Curb Sidewalk Pads Pavers & Bollards		11,249.39	0.3334	0.03703700
SIDEWALK 4" / 4"	CONCRETE	PHASE 1 28 - Curb Sidewalk Pads Pavers & Bollards		11,249.39	0.3334	0.03703700
STOP BAR	STOP BAR	PHASE 1 42 - Specialty Work		568.49	1.0000	1.00000000
TS ISLAND 6"	TOPSOIL	PHASE 1 10 - Earthwork		39,857.99	0.5000	0.03703700
TS ISLAND 6"	TOPSOIL	Ph 2 10 - Earthwork		185,010.42	0.5000	0.03703700
TS ISLAND 6"	TOPSOIL			224,868.41	0.5000	0.03703700

Job
Material Summary
All Classes (23) - All Phases (2)
Wed Feb 18, 2026 15:48:05
Page 1 of 1

Material	Structure	Phase	Class	Measure	Section	Multiplier	Quantity
ASPHALT BASE	HD 2.0" / 4.0" / 6.0"	PHASE 1 34 - Asphalt Paving		188,822.06	0.3334	0.03703700	2,3
ASPHALT TOP	HD 2.0" / 4.0" / 6.0"	PHASE 1 34 - Asphalt Paving		188,822.06	0.1667	0.03703700	1,1
CONCRETE	BUILDING 6" / 6"	PHASE 1 14 - Building Related		65,626.14	0.5000	0.03703700	1,2
CONCRETE	CONC PAVE 6" / 6"	PHASE 1 28 - Curb Sidewalk Pads Pavers & Bollards		5,435.78	0.5000	0.03703700	1,1
CONCRETE	SIDEWALK 4" / 4"	PHASE 1 28 - Curb Sidewalk Pads Pavers & Bollards		11,249.39	0.3334	0.03703700	1,1
CONCRETE				82,311.31	Varies	0.03703700	1,4
PAVEMENT MARKING	PAVEMENT MARKING	PHASE 1 42 - Specialty Work		454.73	1.0000	1.00000000	4,1
STONE SUBBASE	BUILDING 6" / 6"	PHASE 1 14 - Building Related		65,626.14	0.5000	0.03703700	1,2
STONE SUBBASE	CONC PAVE 6" / 6"	PHASE 1 28 - Curb Sidewalk Pads Pavers & Bollards		5,435.78	0.5000	0.03703700	1,1
STONE SUBBASE	SIDEWALK 4" / 4"	PHASE 1 28 - Curb Sidewalk Pads Pavers & Bollards		11,249.39	0.3334	0.03703700	1,1
STONE SUBBASE	HD 2.0" / 4.0" / 6.0"	PHASE 1 34 - Asphalt Paving		188,822.06	0.5000	0.03703700	3,4
STONE SUBBASE				271,133.37	Varies	0.03703700	4,9
TOPSOIL	TS ISLAND 6"	PHASE 1 10 - Earthwork		39,857.99	0.5000	0.03703700	7,1
TOPSOIL	TS ISLAND 6"	Ph 2 10 - Earthwork		185,010.42	0.5000	0.03703700	3,4
TOPSOIL				224,868.41	0.5000	0.03703700	4,1
ADA ACCESSIBLE MARKING	ADA ACCESSIBLE MARKING	PHASE 1 42 - Specialty Work		522.91	1.0000	1.00000000	5,1
CURB 6" X 8" X 18"	CURB 6" X 8" X 18"	PHASE 1 28 - Curb Sidewalk Pads Pavers & Bollards		6,300.57	1.0000	1.00000000	6,3
PARKING STALL MARKING	PARKING STALL MARKING	PHASE 1 42 - Specialty Work		5,300.48	1.0000	1.00000000	5,3
STOP BAR	STOP BAR	PHASE 1 42 - Specialty Work		568.49	1.0000	1.00000000	5,1
ADA ACCESSIBLE MARKING SYMBOL	ADA ACCESSIBLE MARKING SYMBOL	PHASE 1 42 - Specialty Work		9.00	1.0000	1.00000000	9,0
BOLLARD 6"	BOLLARD 6"	PHASE 1 28 - Curb Sidewalk Pads Pavers & Bollards		36.00	1.0000	1.00000000	36,0
DIRECTIONAL ARROW	DIRECTIONAL ARROW	PHASE 1 42 - Specialty Work		30.00	1.0000	1.00000000	30,0
BEDDING	PVC 04" SDR26 PIPE	PHASE 1 18 - Sanitary		740.49	1.2500	0.03703700	7,4
BEDDING	HDPE 08" PIPE	PHASE 1 20 - Storm		1,559.35	1.5000	0.03703700	1,6
Bedding	PVC 02" SCH 40 WATER LINE	PHASE 1 22 - Water		1,246.69	1.0000	0.03703700	1,2
Bedding				3,546.53	Varies	0.03703700	3,5
COVER	PVC 04" SDR26 PIPE	PHASE 1 18 - Sanitary		740.49	3.2580	0.03703700	7,4
COVER	HDPE 08" PIPE	PHASE 1 20 - Storm		1,559.35	4.6983	0.03703700	1,6
Cover	PVC 02" SCH 40 WATER LINE	PHASE 1 22 - Water		1,246.69	2.3353	0.03703700	1,2
Cover				3,546.53	Varies	0.03703700	3,5
DISPLACEMENT	PVC 04" SDR26 PIPE	PHASE 1 18 - Sanitary		740.49	0.0962	0.03703700	7,4
DISPLACEMENT	HDPE 08" PIPE	PHASE 1 20 - Storm		1,559.35	0.4517	0.03703700	1,6
Displacement	PVC 02" SCH 40 WATER LINE	PHASE 1 22 - Water		1,246.69	0.0314	0.03703700	1,2
Displacement				3,546.53	Varies	0.03703700	3,5
SELECT	PVC 04" SDR26 PIPE	PHASE 1 18 - Sanitary		740.49	0.0000	0.03703700	7,4
SELECT	HDPE 08" PIPE	PHASE 1 20 - Storm		1,559.35	0.0000	0.03703700	1,6
Select	PVC 02" SCH 40 WATER LINE	PHASE 1 22 - Water		1,246.69	0.0000	0.03703700	1,2
Select				3,546.53	0.0000	0.03703700	3,5
SPOIL	PVC 04" SDR26 PIPE			740.49			7,4
SPOIL	HDPE 08" PIPE			1,559.35			1,6
Spoil	PVC 02" SCH 40 WATER LINE	PHASE 1 22 - Water		1,246.69	3.3667	0.03703700	1,2
Spoil				3,546.53	Varies	0.03703700	3,5
INLET CATCH BASIN	INLET CATCH BASIN						
PVC 02" WM	PVC 02" WM	PHASE 1 22 - Water		2.00	1.0000	1.00000000	2,0
PVC 02" RPZ	PVC 02" RPZ	PHASE 1 22 - Water		2.00	1.0000	1.00000000	2,0

Job
Material Summary
All Classes (23) - All Phases (2)
Wed Feb 18, 2026 15:48:05
Page 2 of 1

Material	Structure	Phase	Class	Measure	Section	Multiplier	Quantity
PVC 04" SDR26 45 BEND	PVC 04" SDR26 45 BEND	PHASE 1 18 - Sanitary		2.00	1.0000	1.00000000	2,00